Kenya National Highways Authority
Quality Highways, Better Connections
Barabara Plaza, Block A & C, Jomo Kenyatta International Airport (JKIA), Off Airport South Road, along Mazao Road,
P.O Box 49712 - 00100 Nairobi, Tel 020 - 4954000 / 0700 423 606 Email dg@kenha.co.ke / Website www.kenha.co.ke

REF : **KeNHA/R6/211/2021** DATE: **30th December, 2021**

TO : **ALL BIDDERS**

PERFORMANCE BASED CONTRACT FOR MAINTENANCE OF OLKALOU - NYAHURURU (A4) ROAD

SUBJECT: **ADDENDUM NO. 3**

Reference is made to the tender notice published on MYGOV for RACM 3rd Quarter Tenders FY 2021/2022.

Pursuant to the provisions of Clause 10 of the Tendering procedures and Instructions to Tenderers, the following amendment has been made to the Bid Documents.

SECTION VII – BILLS OF QUANTITIES

- Replace BOQ , Bill No. 7 on page 266 and Bill No. 8 page on 277 with the attached

All other requirements of the tender shall remain the same.

Joseph Kimaru
FOR: DIRECTOR GENERAL
Encl.

07-60-001	Excavate and back fill for gabions in soft materials	M^3	500		
07-60-002	Provide and place gabion boxes and mattresses as specified or as directed by the Engineer	M^2	1,100		
07-60-003	Provide and place rock fill to gabions and mattresses	M^3	200		
07-60-004	Allow for grouting of the rock fill where necessary	M^2	300		
07-60-005	Provide and place 200mm thick stone pitching including grouting to aprons upstream and down stream of bridges and culverts as directed	M^2	9,680		
	Total Carried Forward to Summary:				

29/12/2021

BILL OF QUANTITIES NO. 8
Culvert and Drainage Works

ITEM	DESCRIPTION	UNIT	QUANTITIES BOQ	UNIT BID RATE (KShs)	BID AMOUNT KSh
08-60-033	Provide,lay and join 600mm inner dia concrete pipes	MT	130		
08-60-034	Provide,lay and join 900mm inner dia concrete pipes	MT	36		
08-90-001	Excavate for inlet, out fall, catch water drains, mitre and cut-off drains in soft materail	M^3	1,150		
08-90-003	Excavation in soft material for pipe culverts,headwalls,wing walls,apron,toe walls and drop inlets and compact as specified or as directed by the engineer	m3	212		
08-90-008	Provide and place class 15/20 concrete to beds	M^3	39		
08-90-009	Provide and place class 25/20 concrete to headwalls, wing walls, aprons, surrounds to walls, inlets and outlets to pipe culverts including formwork	M^3	149		
	Total Carried Forward to Summary:				

29/12/2024